BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2017-18/OW/WORK_INDENT29458

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/24/2017-18, Date: 21.02.2018

Construction of RCC Drain at Uttanalappa Layout in Ward No. 09 (Vidyaranyapura) Vidyaranyapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SHARATH S	
				In Figures	In Words
1	201.4	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	185.12	Rupees One Hundred Eighty Five and Twelve Paise Only
2	31.8	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5096.14	Rupees Five Thousand Ninety Six and Fourteen Paise Only
3	66.78	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1.5:3) for raft foundation, column footing, main and secondary beams etc complete as per specifications and directions of engineer in charge of the work	Cum	5785	Rupees Five Thousand Seven Hundred Eighty Five Only
4	4.01	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery TMT Bars FE 500 etc complete as per specifications and directions of engineer in charge of the work	Tonne	63465.9	Rupees Sixty Three Thousand Four Hundred Sixty Five and Ninety Paise Only
5	508.8	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	Sqm	306.16	Rupees Three Hundred Six and Sixteen Paise Only
6	190.8	Providing precast slab of 100mm thick including cost of all materials, labour, curing, transportation, loading unloading, etc complete as per specifications and directions of engineer in charge of the work	Sqm	1424	Rupees One Thousand Four Hundred Twenty Four Only

S. Sharath
Signature of the Contractor

19/09
Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

19/09